



# City of New London

Department of Finance-Purchasing Agent  
13 Masonic Street • New London, CT 06320 • Phone (860) 447-5215 • Fax (860) 447-5297

## Request for Proposals

### ADDENDUM 2

Proposal No.: 2020-15

Addendum No.: 2

Date Issued: March 31, 2020

### Independent Testing Services for New London High School

Opening Date and Time: ~~March 27, 2020 at 2:00 P.M.~~ April 3, 2020 at 2 P.M.

**Bidders Notes:** This addendum is issued to provide all potential bidders with notification of date change from March 27, 2020 at 2PM to April 3, 2020 at 2PM. It is also to inform potential bidders that hard copy proposals are still being accepted, however electronic copies will also be accepted. **If a proposal is submitted electronically, all three (3) emails MUST be copied [Jchapman@newlondonct.org](mailto:Jchapman@newlondonct.org), [Dmcneil@crec.org](mailto:Dmcneil@crec.org) AND [DAS.SCGpublicbids@ct.gov](mailto:DAS.SCGpublicbids@ct.gov) with the proposal number 2020-15 written in the subject line. If this is not adhered to, the submission will not be accepted. Please ensure your qualifications and fee proposal are two (2) separate attachments.**

Attachment "G" has been revised and the below should be used to replace the original.

All other terms and conditions remain the same.

**This Addendum cover page must be signed and returned with your bid.**

\_\_\_\_\_  
Authorized Signature of Bidder

\_\_\_\_\_  
Company Name

Bids cannot be accepted after the Bid Opening Date and Time indicated above.

# Exhibit G

Task Description	Unit	Estimated Qty.	Unit Price	Extension
<b><u>Soils &amp; Foundations</u></b>				
Witness Soil Placement/Compaction Tests. Includes Statement of Special Inspections (SSI) Soils & Foundation section items 1,2 & 4.	Full Day	10		
Witness Soil Placement/Compaction Tests. Includes Statement of Special Inspections (SSI) Soils & Foundation section items 1,2 & 4.	1/2 Day	30		
Gradation/Sieve Analysis	Each	10		
Density Test Equipment	Each	30		
Proctor Density Test	Each	10		
#200 Sieve Wash	Each	10		
Grain Size Distribution Cure	Each	10		
¾" Correction	Each	10		
Soils Description & Identification	Each	10		
Pick-up Samples	Trip	N/A		Included w/above unit prices
Priority Lab Results/report	Each	10		
<b><u>Concrete</u></b>				
Witness Concrete Placement (include slump, air, temperature, truck timing, unlimited #of cylinder fabrication and pickup). SSI Cast -in-place-concrete items #1, 7, 8, & 9.	Full Day	10		

Witness Concrete Placement (include slump, air, temperature, truck timing, unlimited #of cylinder fabrication and pickup). SSI Cast -in- place-concrete items #1, 7, 8, & 9.	1/2 Day	40		
Inspection of Formwork, rebar, concrete cover and preparation. SSI Cast-in-Place-Concrete items #2, 3, 4, 5 & 6.	Full Day	5,		
Inspection of Formwork, rebar, concrete cover and preparation. SSI Cast-in-Place-Concrete items #2, 3, 4, 5 & 6.	1/2 Day	20		
Concrete Flatness & Levelness Per ASTM E1155, “profileograph” or “dipstick” including all reporting	Full Day	2		
Concrete Flatness & Levelness Per ASTM E1155, “profileograph” or “dipstick” including all reporting	1/2 Day	2		
Cylinder Tests (curing and compression testing)	Each	200		
Priority Lab Results/report	Each	10		
<u>Spray on Fireproofing</u>				
Field Inspection, SSI Spray-Applied Fire- Resistant Material items #1-11.	Full Day	2		
Field Inspection, SSI Spray-Applied Fire- Resistant Material items #1-11.	1/2 Day	5		
<b><u>Structural Steel</u></b>				
Field/Shop Inspection, SSI Structural Steel items #1 & 2.	Full Day	3		

Field/Shop Inspection, SSI Structural Steel items #1 & 2.	1/2 Day	3		
Certified Steel Inspector for field installation inspections. SSI Structural Steel items #3-9.	Full Day	3		
Certified Steel Inspector for field installation inspections. SSI Structural Steel items #3-9.	1/2 Day	5		
Non-Shrink Grout Tests	Each	24		
Ultrasonic Testing	Each	1		
Magnetic Particle Examination (Level II)	Each	1		
Coating Thickness	Each	1		
Liquid Dye Penetration Tests	Each	1		
<b><u>Masonry</u></b>				
Field Masonry Inspection (Including but not limited to, reinforcing, anchors, cast stone, masonry units, precast, fabrication of mortar and grout cubes, weather protection, etc.) SSI Masonry items 1-10.	Full Day	10		
Field Masonry Inspection (Including but not limited to, reinforcing, anchors, cast stone, masonry units, precast, fabrication of mortar and grout cubes, weather protection, etc.) SSI Masonry items 1-10.	1/2 Day	25		
Mortar Cube Tests	Each	10		
Grout Prism Test	Each	10		
CMU Block Test	Each	5		
Cast Stone (in accordance with ASTM C1364	Each	1		

Addendum #2  
2020-15

<b>Cold Form Steel Framing</b>				
Field Inspection, SSI Cold-Formed Steel Framing items #1-9.	Full Day	3		
Field Inspection, SSI Cold-Formed Steel Framing items #1-9.	1/2 Day	10		
<b>Site Work -Asphalt</b>				
Field Inspections (Thickness, Compaction)	Full Day	3		
Field Inspections (Thickness, Compaction)	1/2 Day	6		
Density Test	Each	3		
Content & Aggregate Gradation Testing	Each	1		
Priority Lab Results/report	Each	1		
<b>Combination Rate</b>				
Masonry/Concrete/Soils/Asphalt	Full Day	1		
Masonry/Concrete/Soils/Asphalt	1/2 Day	1		
<b>Moisture Emission/pH Testing</b>				
Set-Up	Full Day	1		
Set-Up	1/2 Day	1		
Moisture Emission Testing (calcium chloride test, ASTM F 1869	Each	1		
pH Testing	Each	1		
RH Testing (in-situ probes, ASTM F 2170)	Each	1		