



City of New London

Department of Finance-Purchasing Agent
13 Masonic Street • New London, CT 06320 • Phone (860) 447-5215 • Fax (860) 447-5297

Invitation for Bids

ADDENDUM 1

Proposal No.: 2021-03

Addendum No.: 1

Date Issued: October 13, 2020

**Intersection Improvements Tilley St. at Green St. and Bank St.
State Project 094-260**

Opening Date and Time: October 20, 2020 at 2:00PM

Bidders Notes: This addendum is issued to provide all potential bidders with the bid form to submit their costs.

All other terms and conditions remain the same.

This Addendum cover page must be signed and returned with your bid.

Authorized Signature of Bidder

Company Name

Return Bid To:

Julie Chapman
City of New London
13 Masonic Street
New London, CT 06320

Bids cannot be accepted after the Bid Opening Date and Time indicated above.

Bid Form
2021-03 Tilley/Green/Bank St. Intersection Improvements
State Project 094-260

ITEM NO.	ITEM/DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
0201001A	Clearing and Grubbing (\pm 2%)	L.S.	1		
0202512	Cut Concrete Sidewalk	LF	75		
0202452A	Test Pits	Ea.	8		
0219011A	Sedimentation Control at Catch Basin	Ea.	10		
0202529	Cut Bituminous Concrete Pavement	LF	100		
0406003A	Pavement Repair	SY	200		
0507781	Reset Manhole	Ea.	1		
0811001	Concrete Curbing	LF	200		
0901003A	4" Steel Bollard	Ea.	3		
0921001	Concrete Sidewalk	SF	125		
0921005	Concrete Sidewalk Ramp	SF	500		
0921039	Detectable Warning Strip	Ea.	5		
0922050A	Decorative Crosswalk	SF	480		
0969060A	Construction Field Office (Small)	Month	4		
0970006	Trafficperson (Municipal Police Officer)	Est. Cost	1		
0971001A	Maintenance & Protection of Traffic (\pm 3%)	L.S.	1		
0975004	Mobilization and Project Closeout (\pm 6%)	L.S.	1		
0976002	Barricade Warning Lights - High Intensity	Day	120		

Bid Form
2021-03 Tilley/Green/Bank St. Intersection Improvements
State Project 094-260

ITEM NO.	ITEM/DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
0977001	Traffic Cone	Ea.	60		
0978002	Traffic Drum	Ea.	30		
0979003	Construction Barricade Type III	Ea.	6		
0980001	Construction Staking (± 1%)	L.S.	1		
1001001A	Trenching and Backfilling	LF	1,100		
1001004	Rock in Trench Excavation 0'-4" Deep	CY	15		
1002015	Rock in Foundation Excavation	VF	10		
1102202A	Traffic Control Foundation - Mast Arm	Ea.	4		
1002203	Traffic Control Foundation - Pedestal - Type I	Ea.	11		
1002208	Traffic Control Foundation - Controller - Type IV	Ea.	1		
1008015	2" Rigid Metal Conduit - Surface	LF	40		
1008115	2" Rigid Metal Conduit in Trench	LF	350		
1008117	3" Rigid Metal Conduit in Trench	LF	80		
1008215	2" Rigid Metal Conduit Under Roadway	LF	1100		
1008217	3" Rigid Metal Conduit Under Roadway	LF	375		
1010001	Concrete Handhole	Ea.	9		
1010021	Concrete Handhole - Type 2	Ea.	13		
1010052	Cast Iron Handhole Cover	Ea.	9		

Bid Form
2021-03 Tilley/Green/Bank St. Intersection Improvements
State Project 094-260

ITEM NO.	ITEM/DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
1010054	Cast Iron Handhole Cover - Type 2	Ea.	13		
1102002A	8' Aluminum Pedestal	Ea.	9		
1102010A	12' Aluminum Pedestal	Ea.	2		
1104026A	25' Steel Mast Arm Assembly	Ea.	1		
1104028A	30' Steel Mast Arm Assembly	Ea.	1		
1104037A	45' Steel Mast Arm Assembly	Ea.	2		
1105103A	1 Way, 3 Section Mast Arm Signal	Ea.	17		
1105303A	1 Way, 3 Section Pedestal Mounted Signal	Ea.	2		
1106002A	2 Way Pedestrian Signal Pole Mounted	Ea.	1		
1106003A	1 Way Pedestrian Signal Pedestal Mounted	Ea.	6		
1106004A	2 Way Pedestrian Signal Pedestal Mounted	Ea.	3		
1107006	Pre-Emption Push button	Ea.	1		
1107011A	Accessible Pedestrian Signal and Detector (Type A)	Ea.	14		
1108115A	Full Actuated Controller 8 Phase	Ea.	1		
1108724A	Phase Selector	Ea.	3		
1111201A	Temporary Detection (Site No. 1)	L.S.	1		
1112284A	Vehicle Detection Monitor	Ea.	3		
1112286A	360 Degree Camera Assembly	Ea.	3		

Bid Form
2021-03 Tilley/Green/Bank St. Intersection Improvements
State Project 094-260

ITEM NO.	ITEM/DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
1112287A	360 Degree Video Detection Processor	Ea.	3		
1112410A	Detector Type A	Ea.	5		
1112470A	Pre-Emption System Chasis	Ea.	2		
1113004	2 Conductor, No. 8 AWG Type SE Style TW	LF	250		
1113102	5 Conductor, No. 14 Cable	LF	6500		
1113103	7 Conductor, No. 14 Cable	LF	3200		
1113550A	Detector Cable Optical	LF	1900		
1113725A	23 AWG 4 Twisted Pair Category 6 Cable	LF	750		
1118012A	Removal and/or Relocation of Traffic Signal Equipment	L.S.	1		
1118051A	Temporary Signalization (Site No. 1)	L.S.	1		
1206023A	Removal and Relocation of Existing Signs	L.S.	1		
1208931A	Sign Face - Sheet Aluminum - Type IX Retro-Reflective Sheeting	SF	36		
1210101	4" White Epoxy Resin Pavement Markings	LF	550		
1210102	4" Yellow Epoxy Resin Pavement Markings	LF	1000		
1210107	8" Yellow Epoxy Resin Pavement Markings	LF	25		
1210118	Epoxy Resin Pavement Markings, Symbols and Legends	SF	1500		
1211001	Removal of Pavement Markings	SF	2300		
1220027	Construction Signs	SF	525		

Bid Form
2021-03 Tilley/Green/Bank St. Intersection Improvements
State Project 094-260

ITEM NO.	ITEM/DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
2020 CONTRACT ITEMS TOTAL					